

NO.	DESCRIPTION	QTY	UNIT
1	SHRUBS - 5 GALLON	465	EA
2	TREES - 3" - 6" CALIPER	8	EA
3	CONCRETE PLANTER WALL - 18" TALL	266	LF
4	DECOMPOSED GRANITE - 2" MIN. DEPTH	11,159	SF
5	CONCRETE PAVING - MATCH EXISTING	8,587	SF
6	FURNITURE - LOUNGE CHAIRS	16	EA
7	FURNITURE - 6' BENCH	3	EA
8	CONCRETE - INTEGRAL COLOR	6,900	SF
9	FURNITURE - UMBRELLAS	7	EA
10	FURNITURE - CHIPMAN TABLE	17	EA
11	FURNITURE - CHIPMAN CHAIR	64	EA
12	SANDBLASTED "YC" LOGO	1	EA
13	TENSILE SHADE STRUCTURE & FABRIC	1	EA
14	4" TUBE STEEL FRAMING	851	SF

PLANT LEGEND

SYMBOL	COMMON NAME	MIN. CAL.	MAX. W.	QTY
①	SHRUBS - 5 GALLON	5"	5"	465
②	TREES - 3" - 6" CALIPER	3"	6"	8
③	CONCRETE PLANTER WALL - 18" TALL	18"	N/A	266
④	DECOMPOSED GRANITE - 2" MIN. DEPTH	N/A	N/A	11,159
⑤	CONCRETE PAVING - MATCH EXISTING	N/A	N/A	8,587
⑥	FURNITURE - LOUNGE CHAIRS	N/A	N/A	16
⑦	FURNITURE - 6' BENCH	N/A	N/A	3
⑧	CONCRETE - INTEGRAL COLOR	N/A	N/A	6,900
⑨	FURNITURE - UMBRELLAS	N/A	N/A	7
⑩	FURNITURE - CHIPMAN TABLE	N/A	N/A	17
⑪	FURNITURE - CHIPMAN CHAIR	N/A	N/A	64
⑫	SANDBLASTED "YC" LOGO	N/A	N/A	1
⑬	TENSILE SHADE STRUCTURE & FABRIC	N/A	N/A	1
⑭	4" TUBE STEEL FRAMING	N/A	N/A	851

- KEYNOTES**
- 1. LIMIT OF CONSTRUCTION.
 - 2. CONCRETE PLANTER WALL, 18" HEIGHT.
 - 3. CONCRETE RETAINING WALL, 18" HEIGHT.
 - 4. CONCRETE STEPS, 4" HIT RISER x 1" DROP TREAD.
 - 5. GARDEN WALL, 18" HEIGHT.
 - 6. HAZED PLANTER - ENGINEERED WOOD BECOMING SEATING SURFACE, 18" HEIGHT.
 - 7. SHADE STRUCTURE: 4" TUBE STEEL FRAMING W/ 17' X 3' SHADE FABRIC.
 - 8. SITE FURNISHINGS SEE LEGEND.
 - 9. EXISTING FIRE HYDRANT. PROTECT IN PLACE.
 - 10. POLICE CALL STATION. PROTECT IN PLACE.
 - 11. EXISTING CONCRETE PAVING AND WALLS TO BE REMOVED.
 - 12. EXISTING LIGHT POLE TO BE RELOCATED AS NECESSARY.
 - 13. EXISTING UTILITIES.
 - 14. EXISTING BOULDER TO BE RELOCATED.
 - 15. EXISTING BOULDER TO REMAIN.
 - 16. EXISTING GARDEN WALL TO REMAIN.
 - 17. EXISTING TREE TO BE REMOVED.

- MATERIALS LEGEND**
- 1. SANDBLASTED "YC" LOGO.
 - 2. INTEGRAL COLOR CONCRETE PAVING.
 - 3. 2" COMPRESSIVE STRENGTH AND 10% MAX. AIR CONTENT.
 - 4. 2" COMPRESSIVE STRENGTH AND 10% MAX. AIR CONTENT.
 - 5. 2" COMPRESSIVE STRENGTH AND 10% MAX. AIR CONTENT.
 - 6. 2" COMPRESSIVE STRENGTH AND 10% MAX. AIR CONTENT.
 - 7. 2" COMPRESSIVE STRENGTH AND 10% MAX. AIR CONTENT.
 - 8. 2" COMPRESSIVE STRENGTH AND 10% MAX. AIR CONTENT.

- SITE FURNISHINGS**
- 1. CHIPMAN TABLE AND CHAIRS.
 - 2. 6' BENCH.
 - 3. UMBRELLA.
 - 4. LOUNGE CHAIRS W/ SUNBLENDED CUSHIONS BELOW SHADE STRUCTURES.
 - 5. 28" STAY BENCH.
 - 6. 6' BENCH.
 - 7. UMBRELLA.

NOTE: PROVIDE PRICING TO INSTALL TENSILE FABRIC SHADE STRUCTURE AT THE KEY BENCH AMPHITHEATER, THE SCULPTURE GARDEN AMPHITHEATER AND AT THE PERFORMING ARTS PATIO.

NOT FOR CONSTRUCTION